

APPROVED SCHEDULE - B

No. SE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Providing Missing covering Slab at Muneshwara Block, Vemanna Layout and Kallappa Layout in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				K NARASIMHA RAJU	
				In Figures	In Words
1	141.9	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 142 / Item No. 19.1 / PWD SR 2016-17	cum	182.0	Rupees One Hundred Eighty Two Only
2	76.63	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12/ Item No. 4.6 / PWD SR 2016-17	cum	5267.99	Rupees Five Thousand Two Hundred Sixty Seven and Ninety Nine Paise Only
3	42.57	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. Page No. 18 / Item No. 4.48 / PWD SR 2016-17	cum	5692.0	Rupees Five Thousand Six Hundred Ninety Two Only
4	567.6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.31 / PWD SR 2016-17	Sqm	283.68	Rupees Two Hundred Eighty Three and Sixty Eight Paise Only
5	851.4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick Page No. 25 / Item No. 5.31.1/ PWD SR 2016-17	Sqm	608.0	Rupees Six Hundred Eight Only
6	4730	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 Page No. 24 / Item No. 5.22 / PWD SR 2016-17	m	33.88	Rupees Thirty Three and Eighty Eight Paise Only
7	851.4	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5-1.13 Page No. 24 / Item No. 5.18 / PWD SR 2016-17	Sqm	880.0	Rupees Eight Hundred Eighty Only


 Signature of the Contractor


 Executive Engineer
 Byarayanapura Division
 BBMP, Bangalore - 92


 07/04